



H&S - Cost Certainty - Speed of Construction - Consistent Quality

FASTER

SAFER

ON-TIME





One-Roof—Pinewood Structures



H&S - Cost Certainty - Speed of Construction - Consistent Quality

Pinewood Structures' panelised One-Roof room-in-the-roof system not only removes your H&S headaches but also greatly reduces build times – helping you build safer and faster. Just as importantly, One-Roof is fully compliant with new social distancing practices which will now soon form part of all of our normal site work practices. Utilising all the skills and know-how that you would expect from a leading offsite supplier, Pinewood Structures are able to deliver One-Roof with full site installation and craneage on time, each and every time. Pinewood Structures is an STA Gold Accredited timber frame company with almost 40 years of experience, delivering tens of thousands of units to the house building sector.

FASTER



SAFER



ON-TIME



Key Benefits

SPEED OF CONSTRUCTION

Reduced build times, up to 4 roofs in a single day

HEALTH & SAFETY

Less time working at height compared to more traditional methods of construction.

Less manual handling.

Reduced number of operatives required to install.

COST CERTAINTY

With One-Roof you can be confident that your build will not be subject to unexpected additional charges.

CONSISTANT QUALITY

Manufactured in an off-site, controlled environment.

Quality checked throughout the whole production process, ensuring consistency of both quality and performance.

Standard Package

- Supply and install of insulated Spandrel panels for gable and party walls
- Gable panels to achieve a U-Value of 0.25W/m2K
- Supply and install of insulated Structural Roof Panels
- Roof panels to achieve a minimum U-Value of 0.20W/m2K
- Supply and install of Glulam/Steel purlins and ceiling joists
- Install of site supplied GRP Dormers, Chimneys and roof-lights
- Install of site supplied UPVC Fascia and Soffit

We are flexible and can provide a range of options to meet your requirements, such as increased thermal performance of roof panels and the inclusion of dormers, rooflight and GRP chimney supply.



FASTER

SAFER

ON-TIME



Design

Covered by Pinewood's ISO:9001 quality control procedures, we use Autodesk Revit alongside other 3D modelling software to design all our roofs. So, if BIM is important to you, we can easily cater for this. Our technical team have over 20 years' experience in the design of panelised roofs so will be able to assist on any aspect of the design (Call us: 01767 651 218). Each roof is individually designed and is suitable for timber frame, brick and block and concrete frame.

Manufacture

Our dedicated manufacturing facility located in Gamlingay benefits from recent investment in additional machinery, which has allowed us to double our capacity this year. We have plans for this expansion to continue to meet surging demand.

Supply/Install

We offer a full supply and installation service, each project is managed by our directly employed project managers. We work with installation teams across our supply regions who are experienced in erecting our system. Currently our supply area covers the Midlands, South, South West and South East of England with plans to introduce new regions by the end of 2021. Call us on 01767 651 218 to discuss your site's delivery requirements. We will carry out, as part of our package a pre-install check to ensure there are no surprises which may cause delays on the day of install. These checks can be carried out to fit your build program.